




Petra III RF System Controls: A radiation resistant approach



- Introduction and Overview
- PETRA III
- ELWIS
- radiation test
- results
- conclusion



PETRA II -> III





ELWIS at PETRA III RF - a new system of control, interlock and monitoring




Design Goals for high reliability:

- construction of few different universal modules
- error detection of a module must be as easy as possible
- maintenance by plug and play (replacement of module)
- no expert knowledge is needed
- no detailed documentation is needed (except block diagrams)
- avoid long cables
- extensive post-mortem analysis
- no special components (spare parts must be available in 20 years)





ELWIS module:

PXI crate with analogue & digital in/out channels and plug in signal conditioning boxes



example: klystron ELWIS




radiation test of electronics





- Is it possible to install electronics near the cavities in the tunnel of PETRA III to avoid long cables and documentation?
- Experience with PLC at DORIS since more than 9 years
- Rough test with a desktop PC in PETRA II tunnel: It hangs after proton operation.
- Decision to test PXI crate electronics (PC and FPGA) in DORIS III and measure the radiation.
- We expect higher radiation in DORIS III than in PETRA III, so we are on the safe side.
- Readout of dose by the tested equipment itself!
- Calibration of measurement system by TLDs.



assembly




the tested hardware




ESLS-RF meeting Aarhus, 2005-09-21

Stefan Wilke (DESY)

9



locality of test in DORIS III




different positions in DORIS III


Position1



Position3




power of synchrotron radiation from all dipoles (= energyloss per turn of leptons)



$$P[kW] = 88,46270 * \frac{E[GeV]^4}{r[m]} * I[A]$$



comparing radiation from bending magnets PETRA III / DORIS III





E_c : critical energy (divides the photon spectrum into 2 equal halves)


We expect more than 6 times lower dipole radiation in PETRA III than in our test environment DORIS III



Dose, beam current and lifetime in DORIS III in the first 5 days of test



Dose from Dosimentor and TLD in DORIS III over the whole test time



First results

- Dosimeter calibrated by TLD: It shows units in mRad (= 0,01 mGy)
- electronic fails after almost 22 weeks of operation in DORIS III at 3 different positions
- probably it's a fault in memory of the FPGA
- the accumulated dose up to failure amounts nearly 24 Gy



conclusion

- PETRA III will operate from 2009
- new rf system with ELWIS
- at PETRA III we expect low radiation (PETRA III / DORIS III, straight section)
- electronics in tunnel should be possible



Mange Tak!





appendix





a impression of the new hall






The existing PETRA rf-system



changes in the rf distribution



7-cell copper cavities: 16 → 12
 shunt impedance ($M\Omega$): 368 → 276

Normally each transmitter drives 'its' own 6 cavities. Option to run with only one transmitter on all cavities

